| | pproved Qty. | Description | Unit | Approved Tender Rates of NINGANAGOWDA V PATIL ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 10 | 194.7 | Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509 - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work. | Cum | 7318.45 | 1424902.22 | Rupees Seven Thousand Three Hundred Eighteen and Forty Five Paise Only |
| 11 | 192.6 | Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 420.63 | 81013.34 | Rupees Four Hundred Twenty and Sixty Three Paise Only |
| | | | | | 4129145.70 | |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/10

# BRUHAT BANGALORE MAHANAGARA PALIKE

## APPROVED SCHEDULE - B

BBMP/2019-20/OW/WORK_INDENT37103

E/BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

mprovements and Asphalting to Roads at Durga Parameshwari Layout and Surrounding areas in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of NINGANAGOWDA V PATIL ( ) | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| | 775.13 | Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work. | Cum | 231.47 | 179419.34 | Rupees Two Hundred Thirty One and Forty Seven Paise Only |
| | 3726.81 | Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 102.95 | 383675.09 | Rupees One Hundred Two and Ninety Five Paise Only |
| | 910.04 | Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 686.35 | 624605.95 | Rupees Six Hundred Eighty Six and Thirty Five Paise Only |
| | 1420.13 | Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by manual means without disturbing the base and stacking of the debris materials including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 88.24 | 125312.27 | Rupees Eighty Eight and Twenty Four Paise Only |
| | 391.83 | Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work. | Cum | 1851.18 | 725347.86 | Rupees One Thousand Eight Hundred Fifty One and Eighteen Paise Only |
| | 03.63 | Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 33.34 | 56799.02 | Rupees Thirty Three and Thirty Four Paise Only |
| | 18 | Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.3 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work. | Cum | 5134.88 | 437389.08 | Rupees Five Thousand One Hundred Thirty Four and Eighty Eight Paise Only |
| | | Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 4.9 | 23850.75 | Rupees Four and Ninety Paise Only |
| | | Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 13.73 | 66830.78 | Rupees Thirteen and Seventy Three Paise Only |

Contractor



Executive Engineer